


2011-2016 FORD F-250/350/450,6.7L POWERSTROKE CREW CAB & SUPERCAB, 4" DPF BACK, SINGLE SIDE





ITEM	DESCRIPTION	QTY
1	4" EXTENSION PIPE	1
2	OVER AXLE PIPE	1
3	TAIL PIPE	1
4	HANG TIGHT HANGER	1
5	4" BAND CLAMP	2
6	FLANGE GASKET	1
7	7/16" X 1 1/2" BOLT	3
8	3/8" FLAT WASHER	3
9	7/16" LOCK WASHER	3
10	7/16" NUT	3
11	M22X1.5 HEX HEAD PLUG	1
12	EXUAST TIP 5"	1

Refer to this LOT NUMBER when contacting customer service:

PLEASE READ BEFORE STARTING INSTALLATION

While MBRP has made every effort to ensure that all components of this system are of superior quality and properly packaged, it is the installer's responsibility to ensure the following before removal of the factory exhaust:

- that ALL components shown above are present.
- that ALL mating components fit together.
- that there are no damaged components.
- that the system you have purchased is appropriate for your vehicle year, model and configuration.
- that the system will not interfere with any modifications previously installed or planned.
- that you have read and understand these instructions.

If you have any questions or are uncertain about any aspect of the installation of this system to your vehicle please contact your dealer before commencing installation.

S6287 © 12/23

PAGE 1 OF 3



Removal of Stock System



Figure 1




Figure 2



Figure 4

- 1. Apply some penetrating lubricant to all exhaust fasteners, hangers, and rubber insulators.
- 2. Loosen the three (3) nuts securing the extension pipe flange to the overaxle pipe. Refer to Figure 1.
- 3. Remove temperature sensor from over-axle/tail pipe. Remove the factory over-axle/tail pipe.
- 4. Loosen the three (3) nuts securing the extension pipe to the flange directly behind the exhaust filter and remove the extension pipe. Refer to Figure 2.

Installation of MBRP Performance Exhaust

1. The **Extension Pipe** is pre-cut for the 172.4" (crew-cab long-box) wheelbase. Cut the **Extension Pipe** to the appropriate length for the installation vehicle. Refer to Figure 3.





Figure 3

- 2. Mate the **Extension Pipe** flange to the stock exhaust flange with the Gasket between them and fasten the flanges together with the hardware provided. Refer to Figure 4.
- 3. Install the **Hang TightTM Hanger** onto a **4.0**" **Band Clamp** using the procedure shown below. (Hang TightTM Hanger not exactly as shown)



AS INSTALLED ON VEHICLE

S6287 © 12/23

MBRP



Figure 5



Figure 6

- 4. Place the previously assembled **Hang TightTM Hanger** onto the end of the **Over-Axle Pipe**, leaving the clamp loose. Install the **Hang TightTM Hanger** into the factory rubber isolators.
- 5. Install the Over-Axle Pipe onto the Extension Pipe and snug the Hang TightTM Hanger clamp.
- 6. Place the second band clamp loosely onto the **Tail Pipe** and install onto the **Over-Axle Pipe**, inserting the hanger into the rearward factory rubber isolator. **Refer to Figure 5.**
- 7. Install the **Exhaust Tip** using a 17mm wrench.
- 8. Align the exhaust as required and tighten all clamps and connections.
- 9. Fasten temperature sensor to bung on **Over-Axle Pipe** or install the supplied hex head plug (2011-2014 models). **Refer to Figure 6.**
- 10. Ensure that there is adequate clearance around the spare tire or any fuel and brake lines.

Congratulations! You are ready to begin experiencing the improved power, sound, and driving experience of your **MBRP** performance exhaust system. We know you will enjoy your purchase.

\$6287 © 12/23 PAGE 3 OF 3