

OPTIONAL - Construction Service (Tier 3 states) - NASPO part #'s:					
Alabama, Arizona, Arkansas, Florida, Georgia, Louisiana, Mississippi, Nebraska, North Carolina, Oklahoma, South Carolina, South Dakota, Tennessee, Texas, Virginia, Wyoming (Any Freight charges prepaid and added to invoice)					
Effective Date	NASPO PART #	Construction Service	Description (for more description please notice descriptive outlines)	Unit Pricing	Unit Pricing w/ 5% Discount
1/25/2021	21-3954-11	Geo Technical	Complete a geo technical report based on 1 to 4 borings up to 50' deep.	\$12,000	\$11,400.00
1/25/2021	21-3954-12	Off-load & Set Shelter	Supply crane to off-load set building	\$19,500	\$18,525.00
1/25/2021	21-3954-13	Shelter Foundation	6'x9' concrete pad w/ 3'x4' stoop	\$10,500	\$9,975.00
1/25/2021	21-3954-14	Shelter Foundation	10'x12' concrete pad w/ 3'x4' stoop	\$14,250	\$13,537.50
1/25/2021	21-3954-15	Shelter Foundation	12'x16' concrete pad w/ 3'x4' stoop	\$17,100	\$16,245.00
1/25/2021	21-3954-16	Shelter Foundation	12'x20' concrete pad w/ 3'x4' stoop	\$25,650	\$24,367.50
1/25/2021	21-3954-17	Shelter Foundation	12'x24' concrete pad w/ 3'x4' stoop	\$28,500	\$27,075.00
1/25/2021	21-3954-17.5	Shelter Foundation (additional sq ft)	Shelter foundation price to install each additional sq/ft w/ a minimum of 54 sq/ft.	\$98.96	\$94.01
1/25/2021	21-3954-18	Shelter Grounding	Supply and install Shelter ground halo per Motorola R-56	\$6,000	\$5,700.00
1/25/2021	21-3954-27	Tower Foundation (category 12.4)	Install Tower foundation for (1) Sabre 140' 2400SRWD Guyed tower based on presumptive clay w/ (1) pad/pier base and (3) guy anchors 7.37 Cu. Yds.	\$22,500	\$21,375.00
1/25/2021	21-3954-28	Tower Foundation (category 12.5)	Install Tower foundation for (1) Sabre 60' 2400SRWD Guyed tower based on presumptive clay w/ (1) pad/pier base and (3) guy anchors 6.76 Cu. Yds.	\$22,500	\$21,375.00
1/25/2021	21-3954-30	Tower Foundation (category 12.6)	Install Tower foundation for (1) Sabre 140' S3TL-HD self-supporting tower based on presumptive clay w/ (1) Mat/Pier foundation 33.4 Cu. Yds	\$45,090	\$42,835.50
1/25/2021	21-3954-29	Tower Foundation (category 12.7)	Install Tower foundation for (1) Sabre 60' S3TL self-supporting tower based on presumptive clay w/ (1) Pad/Pier foundation 10.4 Cu. Yds	\$22,500	\$21,375.00
1/25/2021	21-3954-31	Tower Foundation (category 12.8)	Install Tower foundation for (1) Sabre 140' Monopole self-supporting tower based on presumptive clay w/ (1) Pad/Pier foundation 31.42 Cu. Yds	\$42,418	\$40,296.63
1/25/2021	21-3954-31.5	Tower Foundation (additional cu yrd)	Additional cu. Yrd pricing for larger pad and pier foundation. This pricing does not include dewatering, poor soil conditions or other foundation designs then a pad/pier foundation or buried mat foundation design	\$2,625	\$2,493.75
1/25/2021	21-3954-19	Tower Grounding	Supply and install tower grounding halo around the base of the new guyed, self-supporting, and guyed towers per Motorola R-56 grounding standards.	\$6,000	\$5,700.00
1/25/2021	21-3954-21	Erect Tower (category 12.4)	Erect one (1) Sabre 140' 2400SRWD Guyed 2' face all-welded 20' sections. (This does not include the install of any mounts, waveguide bridge, A&L material, light kit, or tower painting)	\$24,375	\$23,156.25
1/25/2021	21-3954-22	Erect Tower (category 12.5)	Erect one (1) Sabre 60' 2400SRWD Guyed 2' face all-welded 10' sections. (This does not include the install of any mounts, waveguide bridge, A&L material, light kit, or tower painting)	\$20,625	\$19,593.75
1/25/2021	21-3954-24	Erect Tower (category 12.6)	Erect one (1) Sabre 140' S3TL-HD self-supporting knock down tube leg with angle bracing. (This does not include the install of any mounts, waveguide bridge, A&L material, light kit, or tower painting)	\$34,050	\$32,347.50
1/25/2021	21-3954-23	Erect Tower (category 12.7)	Erect one (1) Sabre 60' S3TL self-supporting tower w/ all welded 10' sections. (This does not include the install of any mounts, waveguide bridge, A&L material, light kit, or tower painting)	\$23,625	\$22,443.75
1/25/2021	21-3954-25	Erect Tower (category 12.8)	Erect (1) Sabre 140' Monopole self-supporting tower with a 16" top dia. & 41.95" base dia. (This does not include the install of any mounts, waveguide bridge, A&L material, light kit, or tower painting)	\$27,600	\$26,220.00
1/25/2021	21-3954-24.5	Erect Tower (per additional ft.)	Erect guyed, self-supporting, or monopoles per additional ft with a minimum of 60'.	\$195.00	\$185.25
1/25/2021	21-3954-26	Electrical	Supply and install h-frame w/ one meter disconnect. Supply and install (2) 3" PVC conduits from the transformer (estimated distance of 100') to the h-frame and (1) 3" PVC conduit from the h-frame to the shelter (includes electrical wire).	\$26,775	\$25,436.25
1/25/2021	21-3954-26.5	Electrical (additional footage)	supply and install additional 2/0 copper stranded wire and PVC conduit per ft. (longer runs will require larger wire and a reasonable equitable adjustment will be required.)	\$105	\$99.75
1/25/2021	21-3954-2	Generator Foundation	install concrete generator pad and propane tank pad (5'x8'x8" pad)	\$5,250	\$4,987.50
1/25/2021	21-3954-1	Generator Hook-up	set generator and connect to building	\$13,125	\$12,468.75
1/25/2021	21-3954-4	Fuel Tank / LP System	Supply and install (1) 1,000 gallon propane tank an fill to 80% capacity	\$5,250	\$4,987.50
1/25/2021	21-3954-5	Compound	Supply and install 500 sq. ft compound w/ rock and weed barrier for a minimum of 25'x25' compound	\$3,516	\$3,340.20
1/25/2021	21-3954-5.5	Compound (additional sq. ft.)	Each additional sq. ft of rock and weed barrier	\$5.63	\$5.35
1/25/2021	21-3954-6	Access Lane	supply and install (1) 12'Wx25'L access road w/ 6" base material and 3" to 4" crushed rock	\$3,375	\$3,206.25
1/25/2021	21-3954-6.5	Access Lane (additional LF)	supply and install (1) additional LF of access road w/ 6" base material and 3" to 4" crushed rock	\$189	\$179.55
1/25/2021	21-3954-7	Fence	Supply and install a minimum of 100' LF of fence 7' tall & (3) strand barb wire w/ dual 8' gate and (1) 4' walk through gate	\$7,500	\$7,125.00
1/25/2021	21-3954-7.5	Fence (additional LF)	Supply and install (1) additional LF of fencing material	\$75	\$71.25
1/25/2021	21-3954-20	Site Grounding	Supply and install site grounding for a 25'x25' to 50'x50' compound area to include tying into (shelter & generator/propane tank halos, and into fence posts) per Motorola R-56 Grounding standards	\$15,750	\$14,962.50
1/25/2021	21-3954-8	Antenna and Line Work - Antenna	Install one (1) omni antenna at 200' AGL and install one (1) 7/8" coax and sweep test	\$3,000	\$2,850.00
1/25/2021	21-3954-9	Antenna and Line Work - MW dish	Install one (1) microwave dish @ 100' AGL, install one (1) EW63 and sweep test.	\$4,425	\$4,203.75
1/25/2021	21-3954-10	ON-SITE PM SUPPORT (per day):	Programs with multiple sites Sabre recommends one (1) Sabre PM on the ground at all times or at the major mile stones of each project. The following pricing is based on a per day basis which includes labor costs, travel, food, lodging, rental care and fuel while on the job) A three (3) day minimum due to two (2) days of travel and one (1) full day on-site.	\$1,125	\$1,068.75